




- 1. FIBERGLASS ROVING IN BOTTOM OF TRENCH
- 2. TRENCH WITH SPOIL PILE
- 3. EROSION CHECK INSTALLED
- 4. MATTING IN DRAINAGEWAY
- 5. CAP STRIP AND COMPLETED EROSION CHECK


SLOPE EROSION CHECK



















ZMIN.

BLANKET/LINER

8" MIN.







CHANNEL CHECK SLOT

SEE CHANNEL

OVERLAP DETAIL

LOCATION AND SPACING OF "U"

STAKES SHALL BE AS PER

USE UPPER TERMINAL

ANCHOR (SEE APPROPRIATE DETAIL)


SHAPED WIRE STAPLES OR WOODEN

MANUFACTURER'S RECOMMENDATIONS


CHANNEL CHECK SLOT

OVERLAP AS PER

MANUFACTURER'S



LOWER TERMINAL ANCHOR



CHANNEL TERMINAL/EROSION STOP

RECOMMENDATIONS CHANNEL INSTALLATION

CHANNEL LINER

(SEE NOTE NO. 4 & 5)

CHANNEL OVERLAP

NOTES

- 1. THE GENERAL NOTES FOR ALL P-2 SERIES STANDARD DRAWINGS (PERMANENT EROSION CONTROL) ARE GIVEN ON STANDARD DRAWING P-2-A (PERMANENT EROSION CONTROL GABIONS & REVERT MATTRESSES).
- 2. ALL EROSION CONTROL MATERIALS SHALL BE DETERMINED BY THE ITD MATERIALS LAB PRIOR TO INSTALLATION. ALL GEOTEXTILES USED FOR EROSION CONTROL BLANKETS AND CHANNEL LINERS SHALL BE SUBJECT TO STANDARD SPECIAL PROVISION (S. S. P.) 718.
- 3. THE LOCATION, SPACING, AND CONFIGURATION OF THE SLOPE OVERLAP, CHANNEL CHECK ANCHOR, UPPER, CHANNEL OVERLAP, AND CHANNEL TERMINAL/EROSION STOP MAY VARY FOR EACH INSTALLATION ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
- 4. AFTER THE BLANKET/LINER HAS BEEN SECURED TO THE GROUND THE COVERED AREA SHOULD BE SPRINKLED WITH WATER AND LIGHTLY ROLLED TO PRESS THE BLANKET/LINER SLIGHTLY INTO THE SOIL. AVOID OVER COMPACTION OF THE SEED BED.
- 5. LINERS FOR CHANNEL INSTALLATIONS SHOULD BE INTITIALLY PLACED AT THE DOWNSTREAM END AND CONSTRUCTED UPSTREAM.
- 6. SLOPE INSTALLATIONS FOR EROSION CONTROL BLANKETS SHOULD BE INSTALLED ON DISTURBED SOIL WITHIN 24 HOURS AFTER SEEDING OR SODDING OR AS DIRECTED BY THE ENGINEER.
- 7. THE RECOMMENDED FUNCTIONAL LIFE OF EROSION CONTROL BLANKETS USED ON SLOPE INSTALLATIONS IS; FOR SLOPES OF 3:1 OR STEEPER, 0 TO 2 YEARS, AND FOR SLOPES FLATTER THAN 3:1, 2 TO 5 YEARS.
- 8. WOOD STAKES OR "U" SHAPED WIRE STAPLES MAY BE USED TO SECURE BOTH SLOPE AND CHANNEL INSTALLATIONS. THE FIBERGLASS ROVING FOR THE EROSION CHECK MUST BE SECURED WITH WIRE STAPLES ONLY, STAKES OR STAPLES MAY BE USED ON THE REST OF THE INSTALLATION.
- 9. WOOD STAKES SHOULD BE A MINIMUM 10" IN LENGTH WITH ONE EDGE OF THE STAKE TAPERED TO A POINT. SEE THE WOODEN STAKE DETAIL. THE "U" SHAPED WIRE STAPLES ARE TO BE INSTALLED AT 90° TO THE SLOPE PLANE. THE WIRE STAPLES SHOULD BE MADE FROM MINIMUM 11 GUAGE STEEL WIRE. SEE THE "WIRE STAPLE DETAIL".
- 10. NOT TO SCALE

7 2240 Y g					
14 2240 11 1	REVISIONS				
1 \ 2.27.96/	NO. DATE E	BY NO. DATE	BY NO. DATE	BY NO. DATE BY	
	① 5-95 M	ISM 🔘 📗	101 1		CADD EILE NO
4. VE OF 10 6	② 2-96 M	ISM ()			CADD FILE NO.
FORD L. MILLE	Ö	Ŏ	Ö	0	p2c_0296.std
THE L.					DRAWING DATE:
					DECEMBER, 1994

TRANSPORTATION DEPARTMENT

IDAHO BOISE, IDAHO



STANDARD DRAWING

REQUIRES STD. DWG P-2-A FORM CATALOG NUMBER STANDARD DRAWING NO.

SHEET 1 OF 1

P-2-C